Note: Site boundry indicated based on OS map only.

PLEASE NOTE:

The contractor must visit the site and be responsible for checking and verifying all dimensions, measurements, levels, existing drain/sewer positions and services prior to the commencement of the work and the manufacture of any purpose made components.

Any discrepancies are to be notified to Work Architecture.

DO NOT SCALE OFF THIS DRAWING.

THE CONTRACTOR IS RESPONSIBLE for ensuring all works comply with the relevant building regulations and/or statutory requirements whether or not they are specifically noted on this plan. This drawing shall be read in conjunction with all relevant consultants and / or specialists drawings / documents. The materials and workmanship of all relevant trades and building operations shall comply with the recommendations of current British Standards and codes of practice.

IF IN DOUBT REFER TO WORK ARCHITECTURE.

As far as reasonably practicable, this design has been prepared in such a way as to reduce the risks to the health and safety of person(s) who may be affected.

This drawing remains the copyright of Work Architecture and may not be copied without prior written permission.

Rev	Date	Details	Drawn by
A	05.10.07	Changes as per planning officers request, tree details added and red line extended to include access from highway.	ESK
B	22.02.08	Changes to planners request: site access widened with 4m radius to access, parking spaces increased. Block A altered to suit new arrangements. Purpose built cycle store added.	ESK
C	20.03.08	Root protection area added. Car parking rearranged and retaining wall moved to allow for RPA. Bike lockers added and timber bin storage area Steps added.	ESK
D	08.05.08	Steps removed, carpark layout rearranged. 3m radius from crown of tree indicated, footpint of Block B altered to avoid 3m radius. Layout of block A and Block B altered. Entrance to site altered 400mm clearence margin either side of 4100mm carriageway. 1200mm wall added to front, 2m x 2m visibility triangle added with name stone. Ramp added. Bike lockers, and timber bin stores added.	ESK

Fitness First

Apartment Block A
5no. apartments
(2no. 1-Bed
3no. 2 bed)

Apartment Block B
6no. apartments
(6no. 1-Bed)

Site boundary as indicated on OS plan.

Section of existing wall to be removed.

Indicative landscaping.

Private amenity area.

Foundations to be dug out by hand in root protection area. Specialist foundations to be used to protect roots and future root growth in RPA.

New retaining wall to boundary of site.

Dotted circle indicates 3m radius from crown of tree.

Dashed circle indicates root protection area (RPA) taken from tree survey.

Sycamore Tree with protection order.

Existing retaining wall around tree

Residential amenity area

13150
Aprox size of crown (taken from topographical survey)

Gate

12no. car parking spaces.

Cycle lockers

Bin Store

New Retaining Wall

Foundations to be dug out by hand in root protection area. Specialist construction to be used to protect roots and future root growth in RPA.

Existing gate to be removed and filled with new wall.

Residential amenity area.

Indicative landscaping.

Wall 1200mm high.

Name stone.

Access/egress to L.A. approval

Gate

Ramp

Lowered curb

Shared surface

CAVENDISH ROAD

43000

R4000

2400

4100

400

7084

17046

6400

6475

Indicated visibility splays

15

13

Site Layout Plan 1:100

Residential Development, Cavendish Road, Bradford
Site Layout Plan

North

1:200 0 2 4 6 8 10 12 14 16m
1:100 0 1 2 3 4 5 6 7 8m
1:50 0 1 2 3 4m

Overland Developments
client

Proposed Residential Development
Cavendish Road
Bradford
project

Site Layout Plan
title

WORK ARCHITECTURE
THE ARCH BARN
ESTATE YARD
HAREWOOD
LEEDS
LS17 9LF
T: 0113 288 6018 F: 0113 387 3890
E: info@work-architects.co.uk

date: 10/08/07	scale: 1:100@A1
job number: 482.06	drawing number: (03) 01 Rev D
drawn by: iC	checked by:
drawing status: Planning	

www.work-architects.co.uk